



City of Grand Forks

Request for Quotation – Addendum 1

Security System Panel Upgrades

RFQ # IT2019-01-RFQ

Date of Issue: April 2, 2019

This addendum is issued prior to the Addendum deadline (April 16, 2019) in accordance with the RFP documents and shall be considered an integral part of the RFP, read together with any addenda previously or subsequently issued.

Overview of Addendum

This addendum removes the Waste Water Treatment Plant from Table 1, the list of sites to be serviced, and adjusts the total anticipated modules count. Timeline of Activities is unchanged.

Description

Supply of all labour, materials, supervision, machines, tools, and any incidentals necessary to provide installation and programming of upgraded alarm panels as described herein.

The municipal buildings listed in Table 1 are planned to receive alarm panel upgrades. Where possible, existing sensors (motion, magnetic contact, etc.) may be re-used. The main logic boards are currently aging DSC units configured on-site. Last year, the City began upgrading to Bosch G-series equipment to facilitate IP-based remote management. A Bosch RPS provisioning system is currently in place, and quoted hardware must be compatible with this platform.

Based on the current DSC configuration, the modules required for this installation are anticipated to be:

		City Hall	Public Library	Art Gallery	Fire Hall	Waste Water Treatment Plant	Public Works Yard	TOTAL
DS-B8512G	Main Panel	1	1	1	1	±	1	6 5
DS-B8103	Can	1	1	1	1	±	1	6 5
DS-D101	Lock Set	1	1	1	1	±	2	7 6
DS-ICPEZTS	Tamper Sw	1	1	1	1	±	2	7 6
IM-1270	Battery	1	1	1	1	±	1	6 5
DS-B208	8 I/P Mod	3	1	2	1	-	2	9
DS-B930	AN Keypad	3	2	1	2	±	5	14 13
DS-B308	8 O/P Mod	-	-	-	-	-	1	1

Table 1